

ROUGH-IN REQUIREMENTS												
SYMBOL	ATTRIBUTE	DESCRIPTION	SHARED SERVICES				PATHWAY FEED	BACK BOX	BOX COVER/RING	MOUNTING	DETAIL REFERENCE	NUMBERED COMMENTS
			TEL	AV	ELEC	SEC						
		CARD READER, STANDARD				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	FLUSH IN WALL, 42" AFF TO CENTER	1 / 7/6 12	1, 3
	IL	CARD READER, INTEGRATED LOCK ASSEMBLY				•	-	-	N/A		11 / 7/6 12	1, 3
	M	CARD READER, MULLION MOUNT				•	(1) 3/4" CONDUIT			MULLION MOUNTED 42" AFF TO CENTER	2 / 7/6 12	1, 3
	P	CARD READER, PEDESTAL MOUNT				•	(1) 3/4" CONDUIT			PEDESTAL MOUNTED 42" TO CENTER	12 / 7/6 13	1, 3
		MAGNETIC DOOR CONTACT, CONCEALED				•	(1) 3/4" CONDUIT			FLUSH MOUNTED, SEE INSTALLATION DETAILS		1, 3
	WG	MAGNETIC DOOR CONTACT, SURFACE MOUNT WIDE GAP				•	(1) 3/4" CONDUIT			SURFACE MOUNTED, SEE INSTALLATION DETAILS		1, 3
		DOOR HOLD OPEN/RELEASE DEVICE				•	(1) 3/4" CONDUIT			REFER TO INSTALLATION DETAILS AND MANUFACTURER INSTALLATION MANUAL FOR MOUNTING INSTRUCTIONS		1, 3
		LOCAL AUDIBLE ALARM				•	(1) 3/4" CONDUIT	THREE GANG SUPER DEEP BOX	THREE GANG	FLUSH IN WALL 42" AFF TO CENTER	3 / 7/6 12	1, 3
	CE	VIDEO CAMERA, FIXED, CEILING MOUNT, ELEVATOR				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	REFER TO INSTALLATION DETAILS AND MANUFACTURER INSTALLATION MANUAL FOR MOUNTING INSTRUCTIONS	1 / 7/6 10	1, 3
	CFA	VIDEO CAMERA, FIXED, CEILING MOUNT, ACCESSIBLE				•	N/A			REFER TO 10.05 FOR MOUNTING DETAILS	2 / 7/6 10	1, 3
	CP	VIDEO CAMERA, FIXED, CEILING PENDANT MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	TWO GANG	CEILING PENDANT MOUNT	4 / 7/6 10	1, 3
	TS	VIDEO CAMERA, FIXED, TRAY MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	TWO GANG	TRAY MOUNT	7 / 7/6 10	1, 3
	WF	VIDEO CAMERA, FIXED, WALL MOUNT, FLUSH				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	REFER TO 10.05 FOR MOUNTING DETAILS	5 / 7/6 10	1, 3, 10
	WS	VIDEO CAMERA, FIXED, WALL MOUNT, SURFACE				•	(1) 1/2" CONDUIT		ONE GANG	REFER TO 10.05 FOR MOUNTING DETAILS	6 / 7/6 10	1, 3, 10
	CFA	VIDEO CAMERA, DUAL IMAGER, CEILING MOUNT, ACCESSIBLE				•	N/A	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	FLUSH MOUNTED TO CEILING	2 / 7/6 10	1, 3
	CP	VIDEO CAMERA, DUAL IMAGER, CEILING PENDANT MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	TWO GANG	CEILING PENDANT MOUNT	4 / 7/6 10	1, 3
	WA	VIDEO CAMERA, DUAL IMAGER, WALL ARM MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	REFER TO INSTALLATION DETAILS AND MANUFACTURER INSTALLATION MANUAL FOR MOUNTING INSTRUCTIONS	9 / 7/6 10	1, 3, 10
	CFA	VIDEO CAMERA, 270-FIXED, CEILING MOUNT, ACCESSIBLE				•	N/A			REFER TO 10.05 FOR MOUNTING DETAILS	2 / 7/6 10	1, 3
	CFI	VIDEO CAMERA, 270-FIXED, CEILING MOUNT, INACCESSIBLE				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	TWO GANG	FLUSH MOUNTED TO CEILING	3 / 7/6 10	1, 3
	CP	VIDEO CAMERA, 270-FIXED, CEILING PENDANT MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	TWO GANG	CEILING PENDANT MOUNT	4 / 7/6 10	1, 3
	SCA	VIDEO CAMERA, 270-FIXED, CORNER WALL ARM MOUNT WITH BRACKET				•	(1) 3/4" CONDUIT	2-GANG BELL BOX		REFER TO 10.05 FOR MOUNTING DETAILS	8 / 7/6 10	1, 3, 10
	WA	VIDEO CAMERA, 270-FIXED, WALL ARM MOUNT WITH BRACKET				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	REFER TO 10.05 FOR MOUNTING DETAILS	9 / 7/6 10	1, 3, 10
	WF	VIDEO CAMERA, 270-FIXED, WALL MOUNT, FLUSH				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	REFER TO 10.05 FOR MOUNTING DETAILS	5 / 7/6 10	1, 3, 10
	WS	VIDEO CAMERA, 270-FIXED, WALL MOUNT, SURFACE				•	(1) 1/2" CONDUIT		ONE GANG	REFER TO 10.05 FOR MOUNTING DETAILS	6 / 7/6 10	1, 3, 10
	CFA	VIDEO CAMERA, 360-FIXED, CEILING MOUNT, ACCESSIBLE				•	N/A			FLUSH MOUNTED TO CEILING	2 / 7/6 10	1, 3
	CFI	VIDEO CAMERA, 360-FIXED, CEILING MOUNT, INACCESSIBLE				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	FLUSH MOUNTED TO CEILING	3 / 7/6 10	1, 3
	SCA	VIDEO CAMERA, 360-FIXED, WALL ARM CORNER MOUNT WITH BRACKET				•	(1) 3/4" CONDUIT	2-GANG BELL BOX		REFER TO 10.05 FOR MOUNTING DETAILS AND 7/6 10/6 FOR ADDITIONAL CONDUIT DETAILS	8 / 7/6 10	1, 3, 10
		GLASS BREAK SENSOR, WALL MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 7/8"D	ONE GANG	SURFACE MOUNTED, 10" AFF	2 / 7/6 11	1, 3
		KEY PAD				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	FLUSH IN WALL 42" AFF TO CENTER	1 / 7/6 14	1, 3
		MOTION DETECTOR, WALL MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	SURFACE MOUNTED, 10" AFF	2 / 7/6 11	1, 3
	V	INTERCOM, PEDESTAL MOUNT WITH VIDEO				•	(1) 3/4" CONDUIT	MANUFACTURER FLUSH BACK BOX	N/A	REFER TO INSTALLATION DETAILS	10 / 7/6 12	1, 3
	BLV	INTERCOM, WALL MOUNT BLUE LIGHT ASSISTANCE UNIT WITH VIDEO				•	(2) 3/4" CONDUITS	MANUFACTURER FLUSH BACK BOX	N/A	REFER TO INSTALLATION DETAILS AND MANUFACTURER INSTALLATION MANUAL FOR MOUNTING INSTRUCTIONS	4 / 7/6 11	1, 3, 6
	V	INTERCOM, WALL MOUNT WITH VIDEO				•	(1) 3/4" CONDUIT	MANUFACTURER FLUSH BACK BOX	N/A	REFER TO 7/6 10/7/6 13 FOR MOUNTING DETAILS	5 / 7/6 13	1, 3
		GLASS BREAK SENSOR, CEILING MOUNT				•	(1) 3/4" CONDUIT	SQUARE BOX, 4" SQ X 2 1/8"D	ONE GANG	FLUSH MOUNTED TO CEILING	1 / 7/6 11	1, 3

GENERAL COMMENTS:

- A. OUTLET HEIGHTS SHOWN IN THIS SCHEDULE ARE DEFAULT. REFER TO ARCHITECTURAL DRAWINGS, PARTICULARLY ELEVATIONS, TO CONFIRM ROUGH-IN HEIGHTS. ALSO REFER TO TELECOM PLANS, WHICH MAY SPECIFY A DIFFERENT HEIGHT PER INSTANCE.
- B. PROVIDE BLANK INSERTS IN UNUSED KNOCKOUTS.
- C. AT RATED BARRIERS, PROVIDE FIRESTOPPING/SEALING AROUND BOXES WHERE REQUIRED TO MAINTAIN RATING.
- D. WHEN OUTLET BACK BOXES FACE OPPOSITE SIDES OF A FRAMED WALL, INSTALL BOXES WITH AT LEAST ONE 5/16" BAY OR WITH 24 INCHES OF SEPARATION.
- E. LOCATE TELECOM OUTLETS ADJACENT AND AT THE SAME HEIGHT AS THE CORRESPONDING ELECTRICAL OUTLET. SHARED BACK BOX MOUNTING BRACKETS ARE ACCEPTABLE.

OUTLET/DEVICE CONDUIT REQUIREMENTS:

- F. PROVIDE A DEDICATED CONDUIT STUB PER OUTLET BOX. DO NOT DASH-CHAIN OUTLET BOXES. STUB OUT INTO CEILING SPACE DOES NOT COUNT AS A BEND.
- G. PROVIDE A MINIMUM CONDUIT BEND RADIUS OF SIX TIMES THE INSIDE DIAMETER OF THE CONDUIT.
- H. PROVIDE A PULL BOX AFTER TWO 90-DEGREE BENDS OR 180-DEGREES OF TURNS. THE CONDUIT STUB OUT INTO CEILING SPACE DOES NOT COUNT AS A BEND.
- I. ALLOWABLE CONSOLIDATION OF OUTLET/DEVICE CONDUITS: THE CONSOLIDATED CONDUIT CAPACITY MUST EQUAL TO OR BE GREATER THAN THE AGGREGATE CAPACITY OF THE CONDUITS. PROVIDE A PULL BOX FOR CONDUIT CONSOLIDATION.
- J. PROVIDE A MINIMUM 12" X 12" X 4" PULL BOX FOR OUTLET/DEVICE CONSOLIDATION POINTS.
- K. PROVIDE A PULL STRING IN EACH CONDUIT RUN. LEAVE WORKING SLACK IN THE PULL STRING AT EACH END. Tie OFF SLACK TO PREVENT RECOIL (BACK INTO THE CONDUIT).
- L. WHEN THE OUTLET/DEVICE CONDUIT STUBS OUTSIDE THE ROOM IN WHICH THE OUTLET RESIDES, PROVIDE A LABEL ON THE CONDUIT STUB.

NUMBERED COMMENTS:

1. PROVIDE CONDUIT STUB FROM ACCESSIBLE CEILING SPACE TO BOX. GENERALLY, TURN CONDUIT OUT WITHIN THE SAME ROOM. AVOID PENETRATING RATED BARRIERS - IF A PENETRATION THROUGH A RATED BARRIER IS REQUIRED, THEN MEET THROUGH PENETRATIONS REQUIREMENTS. PROVIDE A PULL STRING PER CONDUIT.
2. PROVIDE CONDUIT FROM ACCESSIBLE CEILING INTO ELEVATOR MACHINE ROOM AND CONNECT TO ELEVATOR CONTROL PANEL. CONDUITS MAY BE CONSOLIDATED AT A BACK BOX (SEE CONSOLIDATION REQUIREMENTS ON 10.02). COORDINATE INSTALLATION WITH THE ELEVATOR INSTALLATION.
3. COORDINATE THE INSTALLATION WITH SPECIALTY EQUIPMENT INSTALLATION (I.E., SECURITY, FIRE ALARM, INCLUDING OUTLET TYPE, INSTALLATION CONFIGURATION (LOCATION, HEIGHT, ETC.), AND CONNECTION TO EQUIPMENT).
4. PROVIDE CONTINUOUS CONDUIT FROM EQUIPMENT/SYSTEM CONTROL PANEL TO NEAREST TELECOMMUNICATIONS PRIMARY PATHWAY. PROVIDE A PULL STRING PER CONDUIT.
5. INSTALL BACK BOX ADJACENT TO POWER OUTLET. COORDINATE INSTALLATION WITH THE ELECTRICAL INSTALLATION. SHARED BOX BRACKETS ARE ACCEPTABLE.
6. OUTLET/BOX SHARED WITH ELECTRICAL. REFER TO ELECTRICAL DRAWINGS FOR OUTLET TYPE AND INSTALLATION REQUIREMENTS. COORDINATE INSTALLATION WITH THE ELECTRICAL INSTALLATION.
7. MOUNT BACK BOX TO THE SIDE OF THE WAP BRACKET.
8. PRIOR TO ROUGH-IN, VERIFY WITH THE SYSTEM VENDOR BACK BOX AND COVERING TYPE AND SIZE REQUIREMENTS. THE BOX AND COVERING TYPE AND SIZES LISTED IN THIS SCHEDULE ARE DEFAULT.
9. BOND BACK BOX TO APPROVED GROUND.
10. MOUNT EXTERIOR WALL MOUNTED CAMERAS AT 10'-0" AFG UNLESS OTHERWISE NOTED. MOUNT INTERIOR WALL MOUNTED CAMERAS AT 8'-0" AFF UNLESS OTHERWISE NOTED.



STAMP



DRW STAMP

REV	DATE	DESCRIPTION
1	09/17/2024	BOX DESIGN DEVELOPMENT
2	09/17/2024	BOX DESIGN DEVELOPMENT
3	09/17/2024	BOX CONSTRUCTION DOCUMENTS
4	09/17/2024	BOX CONSTRUCTION DOCUMENTS
5	09/17/2024	BOX CONSTRUCTION DOCUMENTS
6	09/17/2024	BOX CONSTRUCTION DOCUMENTS
7	09/17/2024	BOX CONSTRUCTION DOCUMENTS
8	09/17/2024	BOX CONSTRUCTION DOCUMENTS
9	09/17/2024	BOX CONSTRUCTION DOCUMENTS
10	09/17/2024	BOX CONSTRUCTION DOCUMENTS
11	09/17/2024	BOX CONSTRUCTION DOCUMENTS
12	09/17/2024	BOX CONSTRUCTION DOCUMENTS
13	09/17/2024	BOX CONSTRUCTION DOCUMENTS
14	09/17/2024	BOX CONSTRUCTION DOCUMENTS
15	09/17/2024	BOX CONSTRUCTION DOCUMENTS
16	09/17/2024	BOX CONSTRUCTION DOCUMENTS
17	09/17/2024	BOX CONSTRUCTION DOCUMENTS
18	09/17/2024	BOX CONSTRUCTION DOCUMENTS
19	09/17/2024	BOX CONSTRUCTION DOCUMENTS
20	09/17/2024	BOX CONSTRUCTION DOCUMENTS
21	09/17/2024	BOX CONSTRUCTION DOCUMENTS
22	09/17/2024	BOX CONSTRUCTION DOCUMENTS
23	09/17/2024	BOX CONSTRUCTION DOCUMENTS
24	09/17/2024	BOX CONSTRUCTION DOCUMENTS
25	09/17/2024	BOX CONSTRUCTION DOCUMENTS
26	09/17/2024	BOX CONSTRUCTION DOCUMENTS
27	09/17/2024	BOX CONSTRUCTION DOCUMENTS
28	09/17/2024	BOX CONSTRUCTION DOCUMENTS
29	09/17/2024	BOX CONSTRUCTION DOCUMENTS
30	09/17/2024	BOX CONSTRUCTION DOCUMENTS
31	09/17/2024	BOX CONSTRUCTION DOCUMENTS
32	09/17/2024	BOX CONSTRUCTION DOCUMENTS
33	09/17/2024	BOX CONSTRUCTION DOCUMENTS
34	09/17/2024	BOX CONSTRUCTION DOCUMENTS
35	09/17/2024	BOX CONSTRUCTION DOCUMENTS
36	09/17/2024	BOX CONSTRUCTION DOCUMENTS
37	09/17/2024	BOX CONSTRUCTION DOCUMENTS
38	09/17/2024	BOX CONSTRUCTION DOCUMENTS
39	09/17/2024	BOX CONSTRUCTION DOCUMENTS
40	09/17/2024	BOX CONSTRUCTION DOCUMENTS
41	09/17/2024	BOX CONSTRUCTION DOCUMENTS
42	09/17/2024	BOX CONSTRUCTION DOCUMENTS
43	09/17/2024	BOX CONSTRUCTION DOCUMENTS
44	09/17/2024	BOX CONSTRUCTION DOCUMENTS
45	09/17/2024	BOX CONSTRUCTION DOCUMENTS
46	09/17/2024	BOX CONSTRUCTION DOCUMENTS
47	09/17/2024	BOX CONSTRUCTION DOCUMENTS
48	09/17/2024	BOX CONSTRUCTION DOCUMENTS
49	09/17/2024	BOX CONSTRUCTION DOCUMENTS
50	09/17/2024	BOX CONSTRUCTION DOCUMENTS
51	09/17/2024	BOX CONSTRUCTION DOCUMENTS
52	09/17/2024	BOX CONSTRUCTION DOCUMENTS
53	09/17/2024	BOX CONSTRUCTION DOCUMENTS
54	09/17/2024	BOX CONSTRUCTION DOCUMENTS
55	09/17/2024	BOX CONSTRUCTION DOCUMENTS
56	09/17/2024	BOX CONSTRUCTION DOCUMENTS
57	09/17/2024	BOX CONSTRUCTION DOCUMENTS
58	09/17/2024	BOX CONSTRUCTION DOCUMENTS
59	09/17/2024	BOX CONSTRUCTION DOCUMENTS
60	09/17/2024	BOX CONSTRUCTION DOCUMENTS
61	09/17/2024	BOX CONSTRUCTION DOCUMENTS
62	09/17/2024	BOX CONSTRUCTION DOCUMENTS
63	09/17/2024	BOX CONSTRUCTION DOCUMENTS
64	09/17/2024	BOX CONSTRUCTION DOCUMENTS
65	09/17/2024	BOX CONSTRUCTION DOCUMENTS
66	09/17/2024	BOX CONSTRUCTION DOCUMENTS
67	09/17/2024	BOX CONSTRUCTION DOCUMENTS
68	09/17/2024	BOX CONSTRUCTION DOCUMENTS
69	09/17/2024	BOX CONSTRUCTION DOCUMENTS
70	09/17/2024	BOX CONSTRUCTION DOCUMENTS
71	09/17/2024	BOX CONSTRUCTION DOCUMENTS
72	09/17/2024	BOX CONSTRUCTION DOCUMENTS
73	09/17/2024	BOX CONSTRUCTION DOCUMENTS
74	09/17/2024	BOX CONSTRUCTION DOCUMENTS
75	09/17/2024	BOX CONSTRUCTION DOCUMENTS
76	09/17/2024	BOX CONSTRUCTION DOCUMENTS
77	09/17/2024	BOX CONSTRUCTION DOCUMENTS
78	09/17/2024	BOX CONSTRUCTION DOCUMENTS
79	09/17/2024	BOX CONSTRUCTION DOCUMENTS
80	09/17/2024	BOX CONSTRUCTION DOCUMENTS
81	09/17/2024	BOX CONSTRUCTION DOCUMENTS
82	09/17/2024	BOX CONSTRUCTION DOCUMENTS
83	09/17/2024	BOX CONSTRUCTION DOCUMENTS
84	09/17/2024	BOX CONSTRUCTION DOCUMENTS
85	09/17/2024	BOX CONSTRUCTION DOCUMENTS
86	09/17/2024	BOX CONSTRUCTION DOCUMENTS
87	09/17/2024	BOX CONSTRUCTION DOCUMENTS
88	09/17/2024	BOX CONSTRUCTION DOCUMENTS
89	09/17/2024	BOX CONSTRUCTION DOCUMENTS
90	09/17/2024	BOX CONSTRUCTION DOCUMENTS
91	09/17/2024	BOX CONSTRUCTION DOCUMENTS
92	09/17/2024	BOX CONSTRUCTION DOCUMENTS
93	09/17/2024	BOX CONSTRUCTION DOCUMENTS
94	09/17/2024	BOX CONSTRUCTION DOCUMENTS
95	09/17/2024	BOX CONSTRUCTION DOCUMENTS
96	09/17/2024	BOX CONSTRUCTION DOCUMENTS
97	09/17/2024	BOX CONSTRUCTION DOCUMENTS
98	09/17/2024	BOX CONSTRUCTION DOCUMENTS
99	09/17/2024	BOX CONSTRUCTION DOCUMENTS
100	09/17/2024	BOX CONSTRUCTION DOCUMENTS

ST. IGNATIUS COLLEGE PREPARATORY

SCHEDULE - ROUGH-IN

T0.03